


इंटरनेट

मानक



Disclosure to Promote the Right To Information

Whereas the Parliament of India has set out to provide a practical regime of right to information for citizens to secure access to information under the control of public authorities, in order to promote transparency and accountability in the working of every public authority, and whereas the attached publication of the Bureau of Indian Standards is of particular interest to the public, particularly disadvantaged communities and those engaged in the pursuit of education and knowledge, the attached public safety standard is made available to promote the timely dissemination of this information in an accurate manner to the public.

“जानने का अधिकार, जीने का अधिकार”

Mazdoor Kisan Shakti Sangathan


“The Right to Information, The Right to Live”

“पुराने को छोड़ नये के तरफ”

Jawaharlal Nehru

“Step Out From the Old to the New”

IS 10421 (1983): Proforma for analysis of unit rate of shuttering/formwork for concrete items [WRD 23: Measurement and Cost Analysis of Works For River Valley Projects]



“ज्ञान से एक नये भारत का निर्माण”

Satyanarayan Gangaram Pitroda

“Invent a New India Using Knowledge”



“ज्ञान एक ऐसा खजाना है जो कभी चुराया नहीं जा सकता है”

Bhartrhari—Nitiśatakam

“Knowledge is such a treasure which cannot be stolen”



BLANK PAGE



IS : 10421 - 1983
(Reaffirmed 1995)

Indian Standard

**PRO FORMA FOR ANALYSIS OF
UNIT RATE OF SHUTTERING/FORMWORK
FOR CONCRETE ITEMS**

(First Reprint OCTOBER 1996)

UDC 69.057.5 : 69.003.12

© *Copyright* 1983

BUREAU OF INDIAN STANDARDS
MANAK BHAVAN, 9 BAHADUR SHAH ZAFAR MARG
NEW DELHI 110002

Indian Standard

**PRO FORMA FOR ANALYSIS OF
UNIT RATE OF SHUTTERING/FORMWORK
FOR CONCRETE ITEMS**

Cost Analysis and Cost Estimates Sectional Committee, BDC 63

Chairman

SHRI S. N. AGNIHOTRI
710, Sector 11-B, Chandigarh

*Members**Representing*

SHRI J. P. AWASTHY CHIEF ENGINEER (DRAINAGE)	Continental Construction (P) Ltd, New Delhi Irrigation Works, Government of Punjab, Chandigarh
DIRECTOR CENTRAL DESIGNS (<i>Alternate</i>)	
CHIEF ENGINEER (MEDIUM IRRIGATION & DESIGNS)	Irrigation & Power Department, Government of Andhra Pradesh, Hyderabad
SUPERINTENDING ENGINEER (<i>Alternate</i>)	
CHIEF ENGINEER (SPECIFIED PROJECT)	Irrigation Department, Government of Maharashtra, Pune
CHIEF ENGINEER (WORKS)	Beas Sutlaj Link Project, Sundernagar
SUPERINTENDING ENGINEER (<i>Alternate</i>)	
DIRECTOR (CMC)	Central Water Commission, New Delhi
DEPUTY DIRECTOR (CMC) (<i>Alternate</i>)	
DIRECTOR (R & C)	Central Water Commission, New Delhi
DEPUTY DIRECTOR (R & C) (<i>Alternate</i>)	
SHRI J. DURAIRAJ	In personal capacity (<i>D-1/141, Satya Marg, New Delhi 110021</i>)
EXECUTIVE ENGINEER (CIVIL)	Kerala State Electricity Board, Trivandrum
GENERAL MANAGER	S. B. Joshi & Co Ltd, Bombay
SHRI R. M. GUPTA	Roads Wing (Ministry of Shipping & Transport), New Delhi
SHRI M. L. MANDAL (<i>Alternate</i>)	
SHRI S. S. IYENGAR	M. N. Dastur & Co (P) Ltd, Calcutta
SHRI N. G. JOSHI	Karnataka Power Corporation Ltd, Bangalore
SHRI A. S. KRISHNASWAMY	Directorate General Border Roads, New Delhi
SHRI H. B. UDASI (<i>Alternate</i>)	
SHRI T. S. MURTHY	National Project Construction Corporation Ltd, New Delhi
SHRI P. D. DUBHASHI (<i>Alternate</i>)	

(*Continued on page 2*)

© Copyright 1983

BUREAU OF INDIAN STANDARDS

This publication is protected under the *Indian Copyright Act (XIV of 1957)* and reproduction in whole or in part by any means except with written permission of the publisher shall be deemed to be an infringement of copyright under the said Act.

(Continued from page 1)

Members

SHRI A. NAGABHUSHANA RAO
SHRI D. M. SAVUR (*Alternate*)
SHRI Y. G. PATEL
SHRI G. A. RAO
SHRI A. S. SEKNON
SHRI G. D. TASKAR
SHRI D. A. KOTHARI (*Alternate*)
SHRI M. THYAGARAJAN
SHRI G. RAMAN,
Director (Civ Engg)

Representing

Hindustan Construction Corporation Ltd, Bombay
Patel Engineering Co Ltd, Bombay
Hindustan Steel Works Construction Ltd, Calcutta
Institution of Engineers, Pathankot
Construction Consultation Services, Bombay
Indian Institute of Public Administration, New Delhi
Director General, ISI (*Ex-officio Member*)

Secretary

SHRI HEMANT KUMAR
Assistant Director (Civ Engg), ISI

Indian Standard

PRO FORMA FOR ANALYSIS OF UNIT RATE OF SHUTTERING/FORMWORK FOR CONCRETE ITEMS

0. FOREWORD

0.1 This Indian Standard was adopted by the Indian Standards Institution on 27 January 1983, after the draft finalized by the Cost Analysis and Cost Estimates Sectional Committee had been approved by the Civil Engineering Division Council.

0.2 Shuttering/formwork for concrete works for river valley projects are boardly of following types:

- a) Panel forms,
- b) Built-in-place forms,
- c) Mobile forms, and
- d) Special forms.

0.2.1 The material for shuttering in all the above cases may either be of steel or timber. Shuttering provided for concrete works may be plain formwork or shuttering of special shapes such as circular, horse-shoe, conic and other shapes required for the structure.

0.3 Struts, braces and ties are required for single or multi-stage depending upon the requirements. The following information will be helpful for a full appreciation of the type and nature of the shuttering work involved:

- a) Name of project,
- b) Name of work,
- c) Layout plan of project,
- d) Location of work,
- e) Purpose of work,
- f) Longitudinal and cross-section,
- g) Construction agency,
 - 1) Departmental or contract

- 2) Name of department/contractor
- h) Volume of concrete work,
- j) Approximate area for shuttering,
- k) Average lead and lift for the formwork,
- m) Type of shuttering,
- n) Normal size of shuttering units used, and
- p) Detailed dimension sketches of special shapes.

NOTE — Detailed plan, elevation and sections of the work and full dimension sketches of the formworks for the whole work as well as for individual units should be provided.

0.4 For the purpose of deciding whether a particular requirement of this standard is complied with, the final value, observed or calculated, expressing the result of a test or analysis, shall be rounded off in accordance with IS : 2-1960*. The number of significant places retained in the rounded off value should be the same as that of the specified value in this standard.

1. SCOPE

1.1 This standard lays down the *pro forma* for analysis of unit rate of shuttering/formwork for concrete items in river valley projects.

2. PRO FORMA

2.1 The *pro forma* recommended for analysis of unit rate of shuttering/formwork for concrete items is as given in Table I.

TABLE I PRO FORMA FOR ANALYSIS OF UNIT RATE OF SHUTTERING/FORMWORK

Details of Shuttering:

- i) Name of work for which shuttering is required
- ii) Quantity of concrete
- iii) Type and shape of shuttering

(Continued)

*Rules for rounding off numerical values (revised).

TABLE 1 PRO FORMA FOR ANALYSIS OF UNIT RATE OF SHUTTERING/FORMWORK — Contd

Item	Unit	Quantity	Rate	Amount	Remarks
(1)	(2)	(3)	(4)	(5)	(6)
(A) STEEL SHUTTERING:					
a) <i>Materials</i>					
i) Steel plates					
ii) Steel sections					
iii) Pipes					
iv) Miscellaneous materials including that required for welding, rivetting, etc					
b) <i>Labour charges for fabrication</i>					
i) Foremen/supervisors					
ii) Welders					
iii) Fitters					
iv) Helpers					
v) Skilled/ordinary labour					
vi) Others					
c) <i>Charges for machinery and equipment including charges for power/gas/diesel</i>					
i) Cutting machine					
ii) Welding/rivetting machine					
iii) Rolling machine					
iv) Air compressors					
v) Others					
d) <i>Maintenance charges of items under (c)</i>					
e) <i>Ancillaries and incidentals</i>					
Proportional cost of the following job facilities:					
i) Labour and staff quarters					
ii) Service roads and transportation arrangements for staff and labourers					
iii) Electric supply					
iv) Water supply					

(Continued)

TABLE 1 PRO FORMA FOR ANALYSIS OF UNIT RATE OF SHUTTERING/FORMWORK — Contd

Item	Unit	Quantity	Rate	Amount	Remarks
(1)	(2)	(3)	(4)	(5)	(6)
v) Sanitary facilities					
vi) Drainage facilities					
vii) Medical facilities					
viii) Other amenities					
f) <i>Maintenance cost of items under clause (e)</i>					
g) <i>Proportional cost of supervisory work establishment</i>					
h) <i>Contingencies</i>					
j) <i>Overhead (excluding profit)*</i>					
Total cost of shuttering					
Area of shuttering					
Number of reuse					
Cost of shuttering/unit/use					
k) <i>Erection cost</i>					
i) Transportation charges					
ii) Labour charges with details					
iii) Materials including oiling, sealing, etc					
iv) Scaffoldings					
v) Machinery charges, if any					
m) <i>Dismantling/stripping cost</i>					
i) Transportation charges					
ii) Labour charges with details					
iii) Machinery charges, if any					
n) <i>Total charges (a to m) of formwork/sq.m chargeable to work</i>					

*This shall include establishment, office stationery, general tools and plants, staff cars, their running and maintenance, insurance, workman's compensation, telephone and telecommunication facilities, consultation services, entertainments, etc

(Continued)

TABLE 1 PRO FORMA FOR ANALYSIS OF UNIT RATE OF SHUTTERING/FORMWORK — Contd

Item	Unit	Quantity	Rate	Amount	Remarks
(1)	(2)	(3)	(4)	(5)	(6)

(B) *WOODEN SHUTTERING:*a) *Materials*

- i) Type of timber
- ii) Wooden joists
- iii) Jigs and joists
- iv) Miscellaneous material

b) *Labour charges*

- i) Foremen/supervisors
- ii) Carpenters
- iii) Labour for creating in position
- iv) Helpers
- v) Other labour, if any.

c) *Charges for machinery and equipment including charges for power/gas/diesel*

- i) Band/circular/trolley saw
- ii) Planer
- iii) Shaper
- iv) Others

d) *Ancillaries and incidentals*

Proportional cost of the following job facilities:

- i) Labour and staff quarters
- ii) Service road and transportation arrangements for staff and labourers
- iii) Electric supply
- iv) Water supply
- v) Sanitary facilities
- vi) Drainage facilities
- vii) Medical facilities
- viii) Other amenities

(*Continued*)

**TABLE 1 PRO FORMA FOR ANALYSIS OF UNIT RATE OF
SHUTTERING/FORMWORK — Contd**

Item	Unit	Quantity	Rate	Amount	Remarks
(1)	(2)	(3)	(4)	(5)	(6)
e) <i>Maintenance of items under (d)</i>					
f) <i>Proportional cost of supervisory work establishment</i>					
g) <i>Contingencies</i>					
h) <i>Overheads (excluding profit)*</i>					
Total cost of shuttering					
Area of shuttering					
Number of reuse					
Cost of shuttering/unit/use					
j) <i>Erection cost</i>					
i) <i>Transportation charges</i>					
ii) <i>Labour charges with details</i>					
iii) <i>Materials including oiling sealing, etc</i>					
iv) <i>Scaffoldings</i>					
v) <i>Machinery charges, if any</i>					
k) <i>Dismantling/stripping cost</i>					
i) <i>Transportation charges</i>					
ii) <i>Labour charges with details</i>					
iii) <i>Machinery charges, if any</i>					
m) <i>Total charges of (a to k) form- work/sq. m chargeable to work</i>					

*Overhead shall include establishment, office stationery, general tools and plants, staff cars, their running and maintenance, insurance, workman's compensation, telephone and telecommunication facilities, consultation service, entertainments, etc.

BUREAU OF INDIAN STANDARDS

Headquarters:

Manak Bhavan, 9 Bahadur Shah Zafar Marg, NEW DELHI 110002

Telephones: 323 0131, 323 8375, 323 9402

Fax : 91 11 3234062, 91 11 3239399

Telegrams : Manaksanstha

(Common to all Offices)

Telephone

Central Laboratory :

Plot No. 20/9, Site IV, Sahibabad Industrial Area, Sahibabad 201010

8-77 00 32

Regional Offices:

Central : Manak Bhavan, 9 Bahadur Shah Zafar Marg, NEW DELHI 110002

323 76 17

*Eastern : 1/14 CIT Scheme VII M, V.I.P. Road, Manikola, CALCUTTA 700054

337 86 62

Northern : SCO 335-336, Sector 34-A, CHANDIGARH 160022

60 38 43

Southern : C.I.T. Campus, IV Cross Road, MADRAS 600113

235 23 15

†Western : Manakalaya, E9, Behind Marol Telephone Exchange, Andheri (East),
MUMBAI 400093

832 92 95

Branch Offices::

'Pushpak', Nurmohamed Shaikh Marg, Khanpur, AHMEDABAD 380001

550 13 48

‡Peenya Industrial Area, 1st Stage, Bangalore-Tumkur Road,
BANGALORE 560058

839 49 55

Gangotri Complex, 5th Floor, Bhadbhada Road, T.T. Nagar, BHOPAL 462003

55 40 21

Plot No. 62-63, Unit VI, Ganga Nagar, BHUBANESHWAR 751001

40 36 27

Kalaikathir Buildings, 670 Avinashi Road, COIMBATORE 641037

21 01 41

Plot No. 43, Sector 16 A, Mathura Road, FARIDABAD 121001

8-28 88 01

Savitri Complex, 116 G.T. Road, GHAZIABAD 201001

8-71 19 96

53/5 Ward No.29, R.G. Barua Road, 5th By-lane, GUWAHATI 781003

54 11 37

5-8-56C, L.N. Gupta Marg, Nampally Station Road, HYDERABAD 500001

20 10 83

E-52, Chitaranjan Marg, C-Scheme, JAIPUR 302001

37 29 25

117/418 B, Sarvodaya Nagar, KANPUR 208005

21 68 76

Seth Bhawan, 2nd Floor, Behind Leela Cinema, Naval Kishore Road,
LUCKNOW 226001

23 89 23

Patliputra Industrial Estate, PATNA 800013

26 23 05

T.C. No. 14/1421, University P. O. Palayam, THIRUVANANTHAPURAM 695034

6 21 17

Inspection Offices (With Sale Point) :

Pushpanjali, 1st Floor, 205-A, West High Court Road, Shankar Nagar Square,
NAGPUR 440010

52 51 71

Institution of Engineers (India) Building 1332 Shivaji Nagar, PUNE 411005

32 36 35

*Sales Office is at 5 Chowringhee Approach, P.O. Princep Street,
CALCUTTA 700072

27 10 85

†Sales Office is at Novelty Chambers, Grant Road, MUMBAI 400007

309 65 28

‡Sales Office is at 'F' Block, Unity Building, Narashimaraja Square,
BANGALORE 560002

222 39 71